




# Regional Recycled Water -Advanced Purification Center

Sun Liang, Ph.D., P.E. Metropolitan Water District of Southern California Zakir Hirani


Stantec

WateReuse LA Chapter Meeting December 5, 2017

## Northern California Runoff



### Upper Colorado River Basin Runoff



# Water Supply Management

Stabilize Imported Supply

- State Water Project Water
- Colorado River Water


Develop Local Supply

- Recycled Water
- Desalinated Waters
- Impaired Groundwater Recovery

#### Conservation


- Supply Allocation
- Financial Incentive

## Joint Outfall System



### JWPCP Wastewater Treatment





Design flow rate 400 MGD; current flow rate 265 MGD

#### Processes:


- Primary clarification
- High purity oxygen activated sludge
- Anaerobic digestion and energy recovery (~20 MW)
- Solid processing: dewatering, drying

Plant produces non-nitrified effluent for ocean disposal

# Approach to the Regional Recycled Water Program

- Perform a study cooperatively to estimate the demand for groundwater augmentation of JWPCP treated recycled water in groundwater basins
- Conduct pilot testing of two advanced water treatment (AWT) process trains to evaluate the feasibility of using JWPCP secondary effluent for groundwater augmentation
- Conduct demonstration plant scale testing
- Take phased approach to full scale facilities
- Allow provisions for off-ramps, if necessary


### **Pilot Treatment Schematic**



# **Pilot Study Results**

- JWPCP non-nitrified secondary effluent can be treated to produce high quality recycled effluent
- UF/RO and MBR/RO permeate water quality met DDW criteria for groundwater recharge with respect to turbidity, TN, TOC, virus, and total *coliform*; however, boron and nitrate are potential concerns due to Basin Plan and SNMP objectives
- MBR/RO was more effective than UF/RO at removing TOC, NDMA, NDPA, NDMAFP, and biodegradable PPCPs
- AOP (UV/H<sub>2</sub>O<sub>2</sub>) achieved the treatment goals of 0.5-log reduction of 1,4-dioxane and effluent levels below the 10 ng/L NL for NDMA and NDPA, but not NDEA. It is likely that higher UV/H<sub>2</sub>O<sub>2</sub> doses than tested would have achieved effluent NDEA levels below NL
- The UF membrane (PVDF) was irreversibly fouled by the end of the two-year test period and RO membranes were susceptible to fouling with non-nitrified JWPCP secondary effluent

# Location of Proposed Facility In Carson



# Regional Recycled Water Program Next Steps

- Complete design, construction, start-up and operations of Advanced Purification Center
- Proceed with facilities planning, engineering, and additional groundwater modeling
- Finalize agreements with Sanitation Districts
- Develop institutional and financial arrangements needed for implementation
- Initiate public outreach effort focused on Advanced Purification Center



SANITATION DISTRICTS OF LOS ANGELES COUNTY

# Advanced Purification Center

#### **Advanced Purification Center Objectives**

- Achieve conditional acceptance of MBR as an alternative treatment technology for a Groundwater Replenishment Reuse Project
- Determine optimum design and operating criteria for fullscale AWT facility and coordinate operations with Sanitation Districts
- Demonstrate ability of the MBR-RO-UV/AOP process train to meet basin plan objectives
- Develop data for Title 22 Engineering Report for regulatory approval
- Provide vehicle for public outreach and acceptance

#### **Advanced Purification Center Design**




Design includes initial unit processes, and provisions for future unit processes

#### **Process Train**

Process train will be MBR-RO-UV/AOP

- Two 0.25 MGD MBR Systems
- A single 2-stage 0.5 MGD RO System
- A single 20 gpm UV/AOP system
- Provisions to add MF, UV and an additional RO system in future
- Provisions to test alternative process technologies at a pilot-scale

#### **Process Schematic**



#### **3D Layout of Advanced Purification Center**

#### **Advanced Purification Center Schedule**

- Final Design Complete March 2017
- Advertised Construction Bid Package March 2017
- MWD Board Action for Construction June 2017
- Construction and Startup 2017/2018
- Testing 2018/2019





# **Backup Slides**

#### Process Schematic for Potential Future AWT Demonstration Facility

