


- Group Annual Report
- 2<sup>nd</sup> Watershed Permit Reuse Findings Update
- Recent Milestones Compliance Summary
- Role of Precipitation on Meeting Nutrient Limits

## Group Annual Report

#### **Group Annual Report (Submitted 4/1/25)**

- Influent Flows and Loads:
  - 21 Quarters worth of data
  - Limited to Plants >10 mgd permitted capacity
- Discharge Flows and Loads:
  - Flows: dry season increased 2% from 2023(4% higher than average)
  - TIN: dry season loads similar the last 4-years (7% less than average)
- Several dischargers continued optimization efforts (e.g., EBMUD)
   and upgrades are in process (e.g., San Mateo, Palo Alto, etc.)
- Recycled Water Volumes: 15% less than 2022
   (attributed to a relatively wet spring in 2023)
- Milestone Reporting






#### Flows for 2023/2024:

- Precipitation Source: https://ggweather.com/sf/monthly.html
- 26 inches of rain (3<sup>rd</sup> highest since sampling began; compared to ~33 inches the previous year)

#### **Baywide TIN Loadings**

- Peak TIN Load: 50,700 kg N/d in 2017
- 2024 dry season: 43,700 kg N/d
- ~15% decline since 2017
- Steady-State TIN discharge since 2021?



# 2nd Watershed Permit Reuse Findings Update

#### WHERE ARE STARTING AT?

- Current Dry Season Discharge Flows to the Bay are Approx. 340 mgd (160,000 AF during the Dry Season)
- Approx. 14% of Current Dry Season Effluent is Recycled (Approx. 25,600 AF)


$$14\% = \frac{25,600 \, AF}{(160,000 \, AF + 25,600 \, AF)}$$

#### WHERE ARE STARTING AT?

- Current Dry Season Discharge Flows to the Bay are Approx. 340 mgd (160,000 AF during the Dry Season)
- Approx. 14% of Current Dry Season Effluent is Recycled (Approx. 25,600 AF)


$$14\% = \frac{25,600 \, AF}{(160,000 \, AF + 25,600 \, AF)}$$

- Current Dry Season Total Inorganic Nitrogen (TIN = ammonia+nitrite+nitrate)
   Discharged to the Bay is Approx. 44,000 kg N/day
- Approx. 7% of this Dry Season Effluent TIN Load is Diverted from the Bay due to Reuse




Confidence level = level of confidence in the values provided. 1 = includes projects that are already in place and/or currently budgeted; 2 = includes projects that are in master planning stages; 3 = includes projects that are conceptual, and 4 = includes projects that are conceptual in nature and require agreements across multiple jurisdictions/agencies.

\* The total net present value might vary from the sum of the listed confidence levels due to rounding.




Confidence level = level of confidence in the values provided. 1 = includes projects that are already in place and/or currently budgeted; 2 = includes projects that are in master planning stages; 3 = includes projects that are conceptual, and 4 = includes projects that are conceptual in nature and require agreements across multiple jurisdictions/agencies.

\* The total net present value might vary from the sum of the listed confidence levels due to rounding.




Confidence level = level of confidence in the values provided. 1 = includes projects that are already in place and/or currently budgeted; 2 = includes projects that are in master planning stages; 3 = includes projects that are conceptual, and 4 = includes projects that are conceptual in nature and require agreements across multiple jurisdictions/agencies.

\* The total net present value might vary from the sum of the listed confidence levels due to rounding.



Confidence level = level of confidence in the values provided. 1 = includes projects that are already in place and/or currently budgeted; 2 = includes projects that are in master planning stages; 3 = includes projects that are conceptual, and 4 = includes projects that are conceptual in nature and require agreements across multiple jurisdictions/agencies.

<sup>\*</sup> The total net present value might vary from the sum of the listed confidence levels due to rounding.



Confidence level = level of confidence in the values provided. 1 = includes projects that are already in place and/or currently budgeted; 2 = includes projects that are in master planning stages; 3 = includes projects that are conceptual, and 4 = includes projects that are conceptual in nature and require agreements across multiple jurisdictions/agencies.

<sup>\*</sup> The total net present value might vary from the sum of the listed confidence levels due to rounding.

#### WHAT DOES THAT TRANSLATE TO IN COST?

Confidence Level	Net Present Value	Comment
Confidence Level 1	\$0.8 billion	Increase from 25,600→36,500 AF
Confidence Level 2	\$0.4 billion	Upwards of 5,600 AF
Confidence Level 3	\$2.3 billion	Upwards of 18,300 AF
Confidence Level 4	\$1.6 billion	Upwards of 12,000 AF
Total	\$5.1 billion	

\$5.1 billion for 7,000 kg N/day diverted from the Bay

# Recent Milestones Compliance Summary

#### **Compliance Milestones Summary**

- Included as an Appendix in the Group Annual Report
   (Submitted on 4/1/25; BACWA Nutrient Watershed Permit Group Annual

   Report for 2023-2024)
- 3<sup>rd</sup> Watershed Permit Requirement (Annual Submission):
  - Status of how each agency is progressing for meeting TIN limits
  - o Specific Milestones Elements:
    - Identify alternatives and perform analyses
    - Compliance plan
    - Schedule/milestones
    - Project details



#### **Compliance Milestones: General Overview**

Table 1. Summary of Questionnaire Results (Color Coded by Grouping; White = Early Actor, Light Grey = Compliance Pathway Identified; Dark Grey = Compliance Alternatives Identified)

A. Discharger <sup>a</sup>	B. ADWF	C. Group <sup>b</sup>	D. Early Actor	E. Will Meet Final Effluent Limit	F. Projects Completed or In-Progress	G. Anticipated Compliance Pathway	H. Prelim. Alternatives Include c					I. Interested	J. Schedule Summary for Projects
	Permitted Capacity (mgd)						NbSd	TTId	OP <sup>d</sup>	RW⁴	NTd	in Purchasing Credits	
American Canyon, City of	2.5	1	Yes	Yes	RW; TTI	-	-	-	-	-	-	- 1	Complete
Benicia, City of	4.5	3	No	-	-	-	Yes	Yes	Yes	Yes	Yes	Maybe	TBD
Burlingame, City of	5.5	3	No	-	-	-	No	Yes	Yes	Yes	No	-	TBD
Central Contra Costa Sanitary District	53.8	3	No	-	-	-	Yes	Yes	No	Yes	Yes	Maybe	TBD
Central Marin Sanitation Agency	10	2	No	-	-	TTI; OP	-	-	-	-	-	-	Alternative to be selected in 2025
City of Richmond Municipal SD	16	1	Yes	Yes	TTI	-	1	-		-	-	-1	TBD
Delta Diablo	19.5	2	No	-	-	TTI; NT	-	-	-	-	-	-	Construction to begin in 2026
EBDA (DSRSD, City of Hayward, City of Livermore, Oro Loma SD, City of San Leandro, Union SD)	107.8	1	Yes	Unsure	NbS; TTI; OP; RW			-			-	Maybe	DSRSD: Complete. Hayward: 2030. Livermore: RW complete, treatment evaluation is underway. Oro Loma SD: Complete. San Leandro: 2026. Union SD: Phases in 2027, 2029, 2031.
EBMUD	120	1	Yes	Unsure	OP			-	-	-	-	-	TBD
Fairfield Suisun SD	23.7	1	Yes	Yes	TTI; OP	•		-	-	-	-	-1	2033
Millbrae, City of	3	2	No	-		RW, NT	-	-	-	-	-	-	Pre-design activities in 2025
Mt. View SD	3.2	1	Yes	Yes	TTI, NbS			-	-		-	*1	Complete, but pursuing additional alternatives with schedule TBD.
Novato SD	7	1	Yes	Unsure	TTI; RW			-	-	-	-	-	Complete
Palo Alto, City of	39	1	Yes	Yes	TTI	-	-	-	-	-	-	-	2028
Pinole, City of	4.06	1	Yes	Yes	TTI	-	-	-	-	-	-	- 1	TBD. Study underway.
Rodeo SD	1.14	3	No	-	-	-	Yes	No	Yes	No	Yes	Yes	TBD
San Jose/Santa Clara WPCP	167	1	Yes	No	TTI; OP; RW		No	Yes	Yes	Yes	No		See individual response
San Mateo, City of	15.7	1	Yes	Yes	TTI	-			-	-	-	-	2025
Sausalito-Marin City SD	1.8	3	No	-	-	•	No	Yes	Yes	Yes	Yes	Maybe	TBD
SD N. 5 of Marin County (Tiburon)	0.98	3	No	-	-		-	Yes	-	-	-	Yes	TBD
Sewerage Agency of Southern Marin	3.6	3	No			-	Yes	No	No	Yes	Yes	Maybe	TBD
SFO Airport	2.2	1	Yes	Yes	TTI; RW			-	-	-	-		TBD. 50 percent design for current phase in 2025.
SFPUC Southeast	85.4	1	Yes	Yes		TTI		-		-	-		TBD. Design-build contractor to be selected 2025.
SFPUC Treasure Island	2.0	1	Yes	Yes	TTI; RW		-	-	-	-	-	-	2026
Silicon Valley Clean Water	29	3	No	-	-		-	Yes	Yes	Yes	-	-	TBD. Evaluating 4 alternatives.
South San Francisco and San Bruno	13	2	No	-		TTI	-	-	-	-	-	-1	TBD. Evaluating process modification alternatives in 2025.
Sunnyvale, City of	29.5	1	Yes	Yes	TTI	•		-	-	-	-	*1	2028
Vallejo Flood and Wastewater District	15.5	2	No	-	-	TTI; NT	-		-	-	Yes	-1	TBD. Evaluating process alternatives in more detail in 2025 and 2026.
West County Wastewater District	12.5	1	Yes	Yes	TTI; OP; RW		-	-		-			Complete
a, Dischargers not included here due to dry season discharge prohibitions: Sonoma Valley County Sanitation District, Napa Sanitation District, City of Petaluma, and Las Gallinas Valley Sanitary District, Other Dischargers not included here: Crockett													

a. Dischargers not included here due to dry season discharge prohibitions: Sonoma Valley County Sanitation District, Napa Sanitation District, City of Petaluma, and Las Gallinas Valley Sanitary District. Other Dischargers not included here: Crockett Community Services District (Port Costa Wastewater Treatment Facility) and Sanitary District Number 5 of Marin County (Paradise Cove Treatment Plant) (see Section 0).

b. Group 1 consists of Early Actors; Group 2 consists of other Dischargers that have identified a compliance pathway; Group 3 consists of other Dischargers that have identified preliminary alternatives.

c. In addition to projects listed under columns F and G.

d. NbS = Nature-based Solutions, TTI = Traditional Treatment Infrastructure; OP = Optimization; RW = Recycled Water, and NT = Nutrient Trading.

#### **Compliance Milestones: Findings**





Figure 3. Distribution of Nutrient Reduction Strategies among Dischargers




### Role of Precipitation on Meeting Nutrient Limits

#### Role of Precipitation on Reuse Demands (Baywide)



Annual Precipitation (Oct - Sept), inches

### Role of Precipitation on Reuse Demands (DSRSD)



Annual Precipitation (Oct - Sept), inches